



Profile XP System Software 4.0.12 Release Notes

Table of Contents

Grass Valley Group Product Support	2
Profile XP Media Platform Features	3
What's new in Version 4.0.12?	5
<i>Tips</i>	
Using Channels in applications	
VdrPanel	
Tool Box Editor	
List Manager	
TimeDelay	
About Time Remaining	
Important RAID considerations	
Updating your PFC500 firmware	
Using redundant RAID controllers	
Configuring NetCentral XP	12
Performance information	13
Fibre Channel network compatibility	
Fibre Channel RAID storage	
Software installation	
Installing Profile XP System Software 4.0.12	
$IIINIGIUUN ETOTUE AF OVNEIN OUTWATE 4.0.17 \dots \dots$	
Updating the RS-422 interface board device driver	15
Updating the RS-422 interface board device driver	15 15
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver	15 15 15
Updating the RS-422 interface board device driver	15 15 15 22
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems	15 15 15 22 23
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup	15 15 15 22 23 23
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services	15 15 22 23 23 23
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording	15 15 22 23 23 23 23
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video	15 15 22 23 23 23 23 23 23
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio	15 15 15 22 23 23 23 23 24 24
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio Profile Applications	15 15 15 22 23 23 23 23 24 24 24
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio Profile Applications Configuration	15 15 15 22 23 23 23 23 24 24 24 24 25
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio Profile Applications Configuration Fibre Channel or Ethernet transfers	15 15 15 22 23 23 23 24 24 24 24 25 26
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio Profile Applications Configuration Fibre Channel or Ethernet transfers Disk Management	15 15 22 23 23 23 24 24 24 25 26 26
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio Profile Applications Configuration Fibre Channel or Ethernet transfers Disk Management Profile Protocol	15 15 22 23 23 23 23 24 24 24 25 26 26 26
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio Profile Applications Configuration Fibre Channel or Ethernet transfers Disk Management Profile Protocol Louth Protocol	15 15 15 22 23 23 23 24 24 24 25 26 26 26 26
Updating the RS-422 interface board device driver Removing the existing RS-422 device driver Installing the RS-422 Board Device Driver Microsoft Windows NT support Known problems Startup Services Recording Video Audio Profile Applications Configuration Fibre Channel or Ethernet transfers Disk Management Profile Protocol	15 15 15 22 23 23 23 24 24 24 25 26 26 26 26 26

Copyright © 2000 Grass Valley Group Inc. All rights reserved. Printed in the United States of America.

This document may not be copied in whole or in part, or otherwise reproduced except as specifically permitted under U.S. copyright law, without the prior written consent of Grass Valley Group Inc., P.O. Box 59900, Nevada City, California 95959-7900

Product options and specifications subject to change without notice. The information in this manual is furnished for informational use only, is subject to change without notice, and should not be construed as a commitment by Grass Valley Group. Grass Valley Group assumes no responsibility or liability for any errors or inaccuracies that may appear in this publication.

Grass Valley, GRASS VALLEY GROUP, Profile and Profile XP are either registered trademarks or trademarks of Grass Valley Group in the United States and/or other countries. Other trademarks used in this document are either registered trademarks or trademarks of the manufacturers or vendors of the associated products. Grass Valley Group products are covered by U.S. and foreign patents, issued and pending. Additional information regarding Grass Valley Group's trademarks and other proprietary rights may be found at www.grassvalleygroup.com www.grassvalleygroup.com.



Grass Valley Group Product Support

You can get technical assistance, check on the status of problems, or report new problems by contacting our Product Support Group.

United States and Canada

Monday–Friday 5:30AM–5:00PM Pacific Time (800) 547-8949

Europe

Monday-Friday 9:00AM-5:30PM

France	01 69 86 83 47	United Kingdom	01628 405830
Germany	0221 9477 446	Other	+44 1628 405840
Italy	02 25086606		

Asia and South America

Australia	02-9888 0100	Japan	81-3-3448-3111
- from overseas	61-2-9888 0100	Korea	82-2-528-5299
Beijing	86-10-62351230	Mexico	52-5-666-6333
	ext. 711	Singapore	65-356-3900
Brazil	55-11-3741-8422	Taiwan	886-2-27571571
Hong Kong	852-25856655		

World Wide

24-hour Emergency Hotline (530) 478-4148 (Contract and warranty customers)

World Wide Web	http://www.grassvalleygroup.com/support/
FTP Site	ftp.grassvalleygroup.com
Users Group	profile-users@grassvalleygroup.com

Profile XP Media Platform Features

Profile XP introduces a new line of Profile Media Platforms. The first in this line, the PVS 1000, provides the following new features, in addition to the outstanding features of the Profile Video File Servers:

Up to eight channels in a single I/O chassis. You can order your PVS 1000 with various combinations of inputs and outputs to meet your specific requirements.

- Fibre Channel RAID is the standard disk storage. Optional redundant power supplies, controllers, and hot-spare drives are available for the Fibre Channel RAID units.
- Increased system bandwidth, allowing eight-channel operation at 50 Mb/s and concurrent Fibre Channel transfers. Additional RAID controllers or chassis are required to attain full system bandwidth.
- Optional redundant power supplies and Windows NT system drives.
- Serial Digital Video I/O, SMPTE 259M with a frame buffer on each input.
- Monitor outputs with text overlay and timecode burn-in capability.
- Flexible Audio formats 16/32 channels of AES/EBU or embedded digital audio. An optional analog audio interface is also available. Audio may be stored in AC3 or Dolby E formats. You must supply the appropriate external encoders and decoders for this compressed audio.
- GPI ports, eight inputs and eight outputs.
- Full Profile API support, including Profile Protocol.
- Compatible with Louth, Odetics, and BVW 75 protocol controllers over RS-422 ports. BVW Insert/Edit operation is not supported.

In addition to a new hardware platform, Profile XP System Software 4.0.12 contains a number of major enhancements:

- The new Configuration Manager lets you create pre-defined channels, which you can use with any Profile XP application. A channel is a set of resources (video and audio inputs and outputs, timecode tracks, encoders and decoders) that you can use with your applications. You can change the resource usage of a channel at any time to meet your needs, or use the factory-default channels for quick initial setup. The *Profile XP Installation Guide* shows the factory-default channels. The *Profile XP System Guide* provides detailed instructions on how to change the defaults.
- All Profile applications, including VdrPanel, now use the channels you create in Configuration Manager to request resources. Conflicts for system resources are reported immediately through easy-to-understand messages. Because of the new central resource management, resources specified by the channel are not assigned until the conflict is resolved.



- The new NetCentral Lite application provides enhanced error reporting tools which allow you to better understand the current state of your Profile XP system. The optional NetCentral Enterprise lets you monitor the status of several Profile XP systems from a central location through SNMP. You can install NetCentral Enterprise on any Windows NT 4.0 system.
- ProLink, the Profile Protocol interpreter for your Profile XP RS-422 ports, now includes more status information in its window. Profile Protocol applications also use channels defined in Configuration Manager, and benefit from the same resource conflict reporting as all the other Profile applications. Although previous Profile Protocol configuration files (*.cfg*) are no longer supported, you can use configuration Manager to create channels called VTR1, VTR2, etc. Your existing application will use the resources specified by these channels in exactly the same way it used the old configuration files.
- VdrPanel has a new look. In addition to its use of channels and central resource management, the VdrPanel interface has been redesigned to make it easier for you to get many panels on the screen at the same time. However, except for the removal of resource assignment tools (crosspoints), all the functions of the old VdrPanel are available in the new one.
- The other Profile applications, Media Manager and the optional TimeDelay, Tool Box Editor, and List Manager, are all are essentially unchanged from the 2.5.X and 3.X releases, except for the addition of central resource management. Contact your Grass Valley Group representative to obtain Profile TimeDelay, Tool Box Editor, or List Manager.
- ContentShare Explorer, based on XML technology, allows you to manage your assets on all the Profile systems at your site and around the world. Read the *ContentShare Explorer User Guide* to learn more about this new tool.
- Grass Valley Group has implemented complete API compatibility between this release and those that preceded it. This should ensure that your third-party Profile application will run on a Profile XP Media Platform with few, if any, changes. However, some basic changes in the Profile XP Media Platform design, such as the absence of external SCSI ports for Profile Library System connections, require Grass Valley Group to not support the following API commands in this release:
 - All TekPls commands
 - All TekVME commands
 - PdrCopyMovie, which has been replaced by the TekXfr streaming transfer commands

NOTE: This version of the Profile SDK does not support development under Microsoft Visual C++ version 6.0. You must use Microsoft Visual C++ version 5.0 with this release.

4

What's new in Version 4.0.12?

This version of Profile System software includes several improvements introduced in this and earlier versions, in addition to correcting some problems that were present in earlier releases,

- **73GB media drive support.** You can now use 73GB media drives in your RAID storage units. The Profile XP System Guide provides information on storage capacities using 73GB drives. Please note that you must use only one size of drive (18, 36, or 73GB) in all the RAID chassis attached to a Profile XP Media Platform. You may not mix drive capacities.
- **Compress VBI option.** If you select the Compress VBI option in the Channel Configuration dialog box in Configuration Manager, all VBI information is compressed along with the active video. 480 lines are compressed for 525/60, 576 lines for 625/50.
- **Improved RS-422 device driver.** This new device driver corrects several problems found in earlier versions of the driver. The new device driver is pre-installed on new systems. If you're installing Version 4.0.12 on an existing system, you should update your RS-422 device driver as described in "Updating the RS-422 interface board device driver" on page 15.
- **Redundant RAID controller.** The optional second RAID controller in a Fibre Channel RAID storage chassis can be used as a redundant controller. Please refer to the *Profile XP System Guide* for information on connecting and using the redundant RAID controller.
- **RAID hot spares.** You can designate some of the drives in your Fibre Channel RAID storage system as hot spares. The *Profile XP System Guide* provides complete instructions on setting up and using hot spare drives. As noted in the *Profile XP System Guide*, hot spares are only available to the RAID controller to which they are connected. If you connect more than one PFC 500 to your Profile XP system, you should configure hot spares for each RAID controller (PFC 500).
- New RAID microcode. The Configuration Manager File System command lets you update the microcode (operating software) on your PFC 500 Fibre Channel RAID storage units.
- **Remote operation.** Profile XP System Software 4.0.12 can be installed on any PC running Windows NT 4.0. This allows you to use Configuration Manager on a PC to manage several Profile XP Media Platforms. You can also run the optional Profile Tool Box (List Manager and Tool Box Editor) and TimeDelay applications on a PC, provided you first install Profile XP System Software 4.0.12.

Tips

The following suggestions may help you get your Profile XP Media Platform on air faster, and keep it running trouble free for a long time.

- **Power up RAID units first.** When you power up your Profile XP Media Platform, be sure to power up your RAID expansion chassis first, then the main RAID chassis. Wait about three minutes to ensure that the RAID units have time to initialize, then power up the Profile XP Media Platform.
- **Don't fill your disks.** This is good advice for any disk-based system, including your PC. Limiting your usage to about 90% of disk capacity will protect you from many potential problems.
- Set audio levels everywhere. Many Profile applications provide ways to set audio record and playback levels. In addition, Configuration Manager lets you set levels or mute audio. Be sure that you have set levels appropriately in your application and in Configuration Manager before suspecting a hardware problem on your audio board.
- Set up Fibre Channel with Louth. In addition to performing your regular Fibre Channel setup tasks as described in the Profile XP System Guide, you must also use VdrPanel to configure Louth Protocol to use streaming transfers over Fibre Channel.

In addition to these short tips, please read the following sections, which will help you manage your Profile XP Media Platform more efficiently.

6

Using Channels in applications

Profile applications supplied with this release require the use of channels created in Configuration Manager to assign resources to the applications. Central resource management manages resource conflicts between all applications that use channels. In addition, resource conflicts with third-party applications that do not use channels will be reported by the applications included in this release.

Existing applications that use Profile API commands to assign resources do not need to be changed to operate with the Profile XP Media Platform.

Similarly, Profile Protocol applications using the Named Configuration Space can continue to use the OpenPort command with a configuration name as a parameter to assign the desired resources to that port. However, the OpenPort command now accepts a channel name instead of a file name to allocate resources to the port. Default channels VTR1, VTR2, VTR3, etc. are configured at the factory, so existing controllers should require no changes. Use Configuration Manger to change the definitions of these channels to meet your needs. New controllers and applications may specify any channel name, provided you create channels with the specified names in Configuration Manger.

Configuration files (*.cfg*) created with a text editor or with the Profile Protocol Resources Utility from previous Profile System Software versions are no longer supported.

The following sections briefly describe how to use channels with each of the applications.

VdrPanel

Select a panel, then choose **Controller | Configure** to select the channel to be used by that panel.

Tool Box Editor

Choose **Config | Select Channels** to select the desired channel definition. The **Config | Resources** command is no longer supported.

List Manager

Choose Config | Select Channels to select the desired channel definition.

TimeDelay

Choose **Config** | **Add Panel**, then select the channel to be used by that channel. To change the channel for an existing panel, click on the panel name, then select the desired channel.



About Time Remaining

The Time Remaining reported by various Profile applications may differ due to the way time remaining is calculated.

Time Remaining is always based on the amount of free disk space available. You can see the remaining disk space by choosing the Storage tab on the Properties page in NetCentral XP.

To calculate Time Remaining from the free disk space, an application may use your current recording bitrate and the number of audio and time code tracks. However, if the application is not currently recording or cannot record, it may make assumptions as to video bitrate and audio and time code requirements. For example, NetCentral XP calculates time remaining based on 15Mb/second recording on one video track with four audio tracks and one time code track. If you typically record at 8Mb/second, for example, your actual time remaining may be almost double the time reported by NetCentral XP.

In addition, Time Remaining is based on the actual media files on your storage system. If you have two clips that refer to the same media files, deleting one of the clips will not free up that space, and the time remaining will not change.

In general, you should use the Time Remaining reported by applications as an indicator only, not a precise number. Use NetCentral XP to see the actual disk space remaining, and avoid filling your storage system to more than 90% of its capacity.

8

Important RAID considerations

In addition to the installation and configuration instructions provided in the *PVS1000 Installation Guide*, the *Profile XP System Guide*, and the *PFC500/E Instruction Manual*, please take a moment to read the following PFC500 Fibre Channel RAID sections. These notes provide instructions not included in other Profile XP documentation.

This version of Profile System Software, together with a new version of the RAID controller microcode, provides the following capabilities:

- You can assign drives as hot spares.
- You can attach up to two RAID expansion chassis to a PFC 500.
- You can use the second controller in a PFC 500 as a redundant controller that will take over control of the RAID chassis should the primary controller fail.

To use these features, you must first update the microcode on all your PFC500 Fibre Channel RAID chassis to the latest version included with this release. The instructions for updating the microcode are included in "Updating your PFC500 firmware" on page 10.

If you wish to use the redundant controller on your PFC 500 chassis, be sure to follow the addressing instructions provided in "Using redundant RAID controllers" on page 11.



Updating your PFC500 firmware

If you upgrading your Profile system software, you must update the microcode on all your PFC 500 Fibre Channel RAID chassis. This will allow to you take advantage of all of the RAID enhancements and benefit from improved reliability.

To update your PFC 500 Fibre Channel RAID microcode:

- 1. Start Configuration Manager and choose File System.
- 2. Click Next twice to open the third page, Disk Utility.
- 3. In the Disk Utility Page 3 of 3, browse for the latest RAID microcode file in the *RAID_Firmware* directory on the CD-ROM. Select the *.bin* file with the highest "flare" or "prom" version number. For example, *flare32104prom202.bin* is more recent than *flare32103prom202.bin* and *flare32103prom203.bin* is more recent than *flare32103prom202.bin*.
- 4. Click **Finish** and wait for the microcode to load.

Disk Utility - Page 3 of 3	×
Disk Utility - Page 3 of 3 RAID controller: Load new microcode only when instructed to by Grass Valley support or release notes.	RAID controller microcode version: 3.21.3 Load new microcode from: C:\profile\microcode\flare32103prom Browse
< <u>B</u> ack	Next > Einish Cancel i

- 5. When the loading is completed, shut down and turn off the power to the Profile XP system *and to all attached PFC 500 Fibre channel RAID chassis*. Failure to shut down the RAID units will prevent the new microcode from taking effect.
- 6. Turn on the power to all the RAID chassis, wait two to three minutes, then turn on the Profile XP system.

Using redundant RAID controllers

Connecting the optional second RAID controller on the PFC 500 Fibre Channel RAID chassis ensures improved availability of your material, since the redundant controller will take over operation of all the attached LUNs if the primary controller fails.

If you decide to use the redundant controller, be sure to follow these instructions.

- 1. Connect your PFC 500 as described in the Profile XP System Guide.
- 2. **Do not** set the Fibre Channel address IDs as described in the *Profile XP System Guide*. All controllers, primary and redundant, must have unique Fibre Channel address IDs. To ensure that all the Fibre Channel address IDs are unique, first assign sequential addresses starting at 0 to all the primary controllers, then continue the sequence, assigning subsequent address IDs to the redundant controllers. Use the following table to determine the correct Fibre Channel address IDs for your PFC 500 Fibre Channel RAID controllers.

Number of PFC500S	PFC500 chassis	Primary controller address ID	Redundant controller address ID
1	First	0	1
2	First	0	2
	Second	1	3
3	First	0	3
	Second	1	4
	Third	2	5

Configuring NetCentral XP

If you wish to use NetCentral XP Lite to monitor your Profile XP Media Platform, or NetCentral XP Enterprise to monitor several Profile XP Media Platforms, you must ensure that the SNMP Trap Destination address on each Profile XP system is correctly set.

Be sure to set the following SNMP Trap Destination addresses.

- The IP address of the local Profile XP Media Platform.
- The IP address of the monitoring station on which you install and run the optional NetCentral XP Enterprise.

NOTE: You must update the SNMP Trap Destination address if you subsequently change the IP address of the local system or the monitoring station.

To set the SNMP Trap Destination addresses on each of your Profile XP Media Platforms:

- 1. Configure the IP address of the Profile XP Media Platform for operation in your network environment as explained in the *Profile XP System Guide*. You must also set the IP address of the monitoring station, usually a PC connected to your Ethernet network.
- 2. On the Profile XP Media Platform, right-click the Network Neighborhood icon, choose **Properties**, then select the Services tab.
- 3. Double-click **SNMP** Properties from the list of services, then choose the **Traps** tab.
- 4. Edit the local IP address in the Traps Destinations list to match the new address of the local system. Add the IP address of the monitoring station if you are using NetCentral XP Enterprise.
- 5. Close all the open Network windows.
- 6. Using **My Computer** or **Windows NT Explorer**, delete the file called *NetCentral.net* from the *c:\profile* directory. This file may not exist if you have never run NetCentral XP.
- 7. Restart the system.

Performance information

Please take note of the following characteristics of your Profile XP Media Platform when installing or operating your system.

Fibre Channel network compatibility

You can connect your Profile XP Media Platform to a Fibre Channel fabric (switched environment) and use Media Manager or any application which uses Profile APIs or FTP over Fibre Channel to move MPEG material to and from Profile XP systems and PDR 300s. Please note the following when using your Profile XP Fibre Channel Video Network.

- You must connect your Profile XP to a Fibre Channel fabric using a Fibre Channel switch. Profile XP does not support connection to a Fibre Channel Arbitrated Loop (Fibre Channel hub).
- If you connect any PDR 300 systems to the same Fibre Channel fabric as your Profile XP, they must use Profile System Software version 2.5.X and switch-compatible microcode (3.0.10).
- Media Manager included with this release can connect to Profile Video File Servers such as the PDR 300. However, the Media Manager included with Profile System Software versions 3.1 or 2.5 cannot connect to or manage clips on a Profile XP Media Platform. You must use Media Manager from Profile System Software version 4.X if you want to manage material on both PDR 300 and Profile XP Media Platforms.

Fibre Channel RAID storage

The Profile XP System Software 4.0.12 provides the following performance when using RAID systems with a single processor module and ten drives:

- 8 channel video @ 15Mbit/s
- 6 channel video @ 20Mbit/s
- 4 channel video @ 25Mbit/s
- 16 channels audio

If your require additional bandwidth, you can add a second PFC 500 and 10 more drives (20 total) to obtain the following performance.

- 8 channels video @ 30Mbit/s
- 6 channels video @ 40Mbit/s
- 4 channels video @ 50Mbit/s

To obtain maximum performance, you must install at least 30 drives on your system. This will provide the following data rates:

• 8 channels video @ 50Mbit/s

Software installation

Profile XP System Software 4.0.12 was installed on your new Profile XP Media Platform at the factory. In normal operation, you should not need to install Profile XP System Software 4.0.12.

If your Profile XP system is operating with an earlier version of Profile XP System Software, you should upgrade to the current version. In addition, if you install a new board in your system, or if you replace a system drive, you may need to re-install the software. Please read and follow these instructions to install the software.

Installing Profile XP System Software 4.0.12

The new Profile XP System Software 4.0.12 installation program includes enhanced features which allow you to update programmable parts on the various Profile XP boards during the installation process. Be sure to read the following instructions as well as the on-screen messages to successfully install this software.

Follow these steps install to Profile XP System Software 4.0.12.

>>> Do not delete the contents of the c:\profile directory before installing Profile XP System Software 4.0.12. Do not use Add/Remove Programs in Control Panel to remove an older version of Profile XP System Software or any Profile applications.

- 1. Log out of the system to ensure that no applications are running.
- 2. Hold the Shift key down during start-up to prevent auto-logon as user profile.
- 3. Log in as *administrator*. The default *administrator* password on a Profile XP system is *triton*.
- 4. Shut down all Profile applications, such as VdrPanel, ProLink, ProNet, etc.
- 5. If you use List Manager or any other application that uses the Event Scheduler Engine and you are upgrading from version 4.0.4 or earlier, delete *master.mmf* from the *c:\profile* directory. Older versions o *mmf* files are not compatible with the new engine.
- 6. Insert the Profile XP System Software 4.0.12 CD-ROM in the CD-ROM reader or connect to a network drive containing the downloaded software.
- 7. The software installation will start automatically. (You may choose to run the *setup.exe* program by choosing **Start | Run** and specifying the appropriate drive.).

NOTE: Be sure to install the software in the default c:\profile directory. *Specifying another location may result in incorrect operation of the software.*

- 8. If an error message appears stating that services could not shut down because there are applications attached, ensure that all applications are closed, then click **OK**. You may safely ignore any subsequent service error messages.
- 9. When the installation process is complete, choose **Yes** when prompted to restart the system.

- 10. Update your PFC 500 RAID chassis microcode as describe on "Updating your PFC 500 firmware" on page 10. If the current microcode version is the same as the version included on the CD-ROM, you do not need to update the microcode.
- 11. Update your RS-422 interface board driver as described in "Updating the RS-422 interface board device driver" on page 15.

Your Profile XP System Software 4.0.12 is installed and ready to use. You should now create an emergency repair disk by inserting a floppy disk in the A drive and running *rdisk.exe*.

Updating the RS-422 interface board device driver

If you are updating your Profile System Software from a version earlier than 4.0.5, you must update your RS-422 interface board driver after you install your new version of Profile System Software.

Removing the existing RS-422 device driver

Before you can install the updated RS-422 device driver, you must first remove the current driver.

- 1. Power On the Profile system and logon as Administrator using these steps.
 - a. Power On the Profile system and hold the **Shift** key down during start-up to prevent auto-logon as user *profile*. Be sure to hold down the shift key until the logon dialog box appears.
 - b. Logon as *administrator*. The factory default *administrator* password on a Profile system is *triton*.
- 2. Open Control Panel by choosing Start | Settings | Control Panel
- 3. Double-click the Network icon.
- 4. The Network dialog box appears. Click the Adapters tab.
- 5. Highlight the Comtrol RocketPort RocketModem and then click the Remove button.
- 6. When prompted "Do you wish to continue?", click Yes.
- 7. Close the Network dialog box.
- 8. Restart the system and logon again as Administrator.

You are now ready to install the updated RS-422 device driver.

Installing the RS-422 Board Device Driver

After removing the old RS-422 board device driver and re-starting the system, you are ready to install the driver for the new RS-422 board. Use the following instructions to install the driver.

To install the RS-422 device driver:




- 1. Make sure you are logged on as *Administrator*. The factory default password on the Profile system for *Administrator* is *triton*.
- 2. Open the Control Panel by choosing Start | Settings | Control Panel.
- 3. Double-click the Network icon.
- 4. The Network dialog box appears. Click the Adapters tab.
- 5. Click the Add button, and then the Have Disk... button.
- 6. When you are prompted, type **c:\profile\drivers\rocket** as the path of the directory containing the driver files (see Figure 1) and click **OK**.

Insert Dis	sk	×
đ	Insert disk with software provided by the software or hardware manufacturer. If the files can be found at a different location, for example on another drive type a new path to the files below.	OK Cancel
	c:\profile\drivers\rocket	

Figure 1. Type the path to the device driver files

7. The Select OEM Option dialog box appears (see Figure 2). Ensure that the Comtrol RocketPort RocketModem is selected, then click **OK**.

Select OEM Option 🛛 🕅
Choose a software supported by this hardware manufacturer's disk.
Comtrol RocketPort/RocketModem
OK Cancel <u>H</u> elp



8. The Add Device Wizard starts. Click **Next** to continue, then select PCI bus as the bus type (see Figure 3) and click **Next** again.

Add Device Wiza	ard	×
	Select the bus type for your board: ISA bus PCI bus	
	< <u>B</u> ack <u>N</u> ext > Cancel Help	,

Figure 3. Select the PCI bus type.

9. Select RocketPort as the board type (see Figure 4), then click Next.

Add Device Wiza	rd	×
	Select your board model: RocketPort	
	< <u>B</u> ack <u>N</u> ext > Cancel	Help

Figure 4. Select RocketPort board model.

Add Device Wiza	rd	×
	How many ports are on the hardware?	
	< <u>B</u> ack <u>N</u> ext > Cancel Help	

10. Select eight ports on the hardware (see Figure 5), then click Next.

Figure 5. Select eight ports.

11. Click Finish to close the Add Devices Wizard (see Figure 6) and open the Device Properties dialog box.



Figure 6. Finish the driver installation.

12. Ensure that the Starting COM Port is set to COM3, then click **OK** to close the Device Properties dialog box (see Figure 7).

Device Properties
Device Setup
RECRETEDERIAL CARDS
Summary
RocketPort - 8 PCI
Name: Rocket #1
ISA Bus Settings
I/O Base Address: N/A
COM Port Range <u>Starting COM Port:</u>
OK Cancel Help

Figure 7. Select COM3 as the starting port.

13. Choose the Options tab in the Comtrol RocketPort/RocketModem Setup dialog box (see Figure 8).

Comtrol RocketPort/RocketModem Setup	? ×
Main Setup Options	1
Configuration	
Image: Complexity of the complexity	
OK Cancel	Help

Figure 8. Choose the Options tab.

14.In the **Options** tab (see Figure 9), set the **Scan Rate(ms)** to 1ms.

Comtrol RocketPort/RocketModem Setup	? ×
Main Setup Options	
Troubleshooting Options ☐ Verbose Event Log	
Performance Adjustments	
<u>S</u> can Rate(ms):	
RS-485 Enable RS-485 options for all devices (NOTE: External RS-232 to RS-485 converters may b required when stardard ports are used in RS-485 mod Defaults	
OK Cance	el Help

Figure 9. Set the scan rate to 1ms.

- 15. Choose **OK** to accept your changes in the RocketPort/RocketModem Setup dialog box.
- 16. Chose **OK** to save new configuration settings and exit the setup.
- 17. Click **Close** in the Network dialog box.
- 18. Restart the system. Logon as *Profile*. The factory default password for the *Profile* user account is *profile*.

Microsoft Windows NT support

Your new Profile XP Media Platform is preloaded with all of the required software, including Windows NT 4.0 with Service Pack 3 and the Year 2000 hotfix. The $c:\i386$ directory contains all the Windows NT 4.0 installation files that normally would be found on the installation diskettes or on the CD-ROM. Profile administrators can use files in this directory if they need to add drivers or other software to the default installation. Service Pack 3 is located in $c:\i386\nt40sp3$. The year 2000 hotfix is located in $c:\i386\nt40sp3$.

If required, you can download Service Pack 3 from the Microsoft FTP site at:

ftp://ftp.microsoft.com/bussys/winnt/winnt-public/fixes

For example, U.S. customers can find instructions on how to download Service Pack 3 in:

ftp://ftp.microsoft.com/bussys/winnt/winnt-public/fixes/usa/nt40/ussp3/

You can obtain the Windows NT 4.0 Year 2000 hotfix from the same Microsoft FTP site. For example, U.S. customers will find the Year 2000 hotfix for Windows NT 4.0 at this location:

ftp://ftp.microsoft.com/bussys/winnt/winnt-public/fixes/usa/nt40/hotfixes-postSP3/y2k2-fix/

Known problems

The following limitations are present in this Profile XP System Software 4.0.12 release. If you wish to obtain more information about these limitations, please mention the reference numbers that follow the description of each limitation.

Startup

Problem	Profile applications such as VdrPanel do not start. The Profile log reports that no filesystem exists.
Workaround	All your RAID units must be powered up before you start your Profile XP Media Platform. Be sure to power up your devices in the following order:
	1.RAID expansion chassis, if present.
	2.Main RAID chassis. Wait three or four minutes.
	3.Profile XP Media Platform.
Problem	The Profile XP system is slow to start when it contains a large number of clips.
Workaround	Profile XP starts more quickly than older Profile systems. However, startup time is proportional to the number of clips loaded on the system.
Problem	Occasionally, after a power up of the system, Configuration Manager does not start.
Workaround	$Restart \ Windows \ NT \ (\textbf{Start Shut Down Restart the computer}).$

Services

Problem	An SNMP application error message may appear when you shut down PDR Access Service (VDR Service), such as when you launch diagnostics or shut down the system without closing applications such as VdrPanel. (10814)
Workaround	You should restart your system if you see this message.

Recording

Problem	VdrPanel may cease to respond if the disk system fills up. (17878)
Workaround	Do not record enough material to fill the disk system. Avoid exceeding approximately 90% of your disk capacity. You can set NetCentral to advise you when your disk system is approaching full capacity.



Video

Problem	Occasionally, playout may be corrupted if you rapidly switch between play, shuttle, and rewind on open-GOP clips. (17773)
Workaround	Normal playout of open-GOP clips preforms as expected at all speeds. If you need to shuttle through material, you should avoid recording open-GOP clips.

Audio

Problem	Audio popping is heard on embedded audio outputs when switching from play back (PB) to E to E if the output is zero-timed.
Workaround	Set output channels to E to E timing, not zero timed.

Profile Applications

Problem	If you delete a clip while it is being used (recorded, played, edited), you may corrupt the media file system. (7696)
Workaround	Do not delete clips while they are in use.
Problem	Media Manager does not correctly show the contents of a remote Profile system after losing and restoring the Ethernet connection to that machine.
Workaround	If you lose an Ethernet connection to any system on your network (disconnected cable, for example), you must reconnect to that machine from all Media Manager sessions on all systems to reestablish proper communications.
Problem	Media Manager does not report the audio compression type on the clip properties page when the clip includes AC3 or Dolby E audio. (17339)
Workaround	No workaround at this time.
Problem	The Media Manager Paste Special command transfers only the clip material between the in and out points of the second and subsequent clips when more than one clip is pasted. (4651)
Workaround	If you wish to transfer all of the clip material of several clips to the destination, use Paste Special on one clip at a time. Use the Transfer Monitor to verify that each transfer is complete before copying and using Paste Special to transfer the next clip.
Problem	List Manager or the Event Scheduler Engine fails to start correctly and error messages concerning <i>master.mmf</i> or the location of the Event Scheduler Engine appear. (8873)
Workaround	Delete <i>master.mmf</i> from the <i>c:\profile</i> directory if you upgraded Profile System Software from a version earlier than 4.0.4. The new engine is unable to use <i>.mmf</i> files from earlier versions.

Problem	Closing the Event Scheduler window by clicking the Close button generates an error message. (18414)
Workaround	Type exit at the command prompt to close the window.
Problem	Clicking the Edit button when the edit list is not open hangs the List Manager application. (17528)
Workaround	There is no workaround at this time.
Problem	The ends of longer NetCentral messages may not be visible in the Log Viewer (WinTail). (7318)
Workaround	Open the NetCentral log file in Notepad or any other text editor to view the complete message.
Problem	If you install NetCentral XP Enterprise, then reinstall Profile XP System Software 4.0.12, NetCentral XP Lite replaces NetCentral XP Enterprise.
Workaround	You must reinstall NetCentral XP Enterprise after installing Profile XP System Software 4.0.12.
Problem	InSync does not copy clips while recording is in progress. (9615)
Workaround	InSync waits for an active recording operation to complete before performing any subsequent copies, including copies of clips recorded on other panels. Avoid very long recording operations and periodically stop all recording to ensure that all of your material is transferred to the backup system.

Configuration

Problem	Configuration Manager falsely shows that the Fibre Channel and Ethernet video network boards are not operational. (18799)
Workaround	The boards should operate correctly. If not, test the boards using by using the Diagnostics as described in the <i>Profile XP Service Manual with NetCentral</i> .
Problem	On a PVS 1008, which has no encoders, LTC is not read on input channels even though the LTC input is assigned in Configuration Manager. (19441)
Workaround	There is no workaround at this time.

Fibre Channel or Ethernet transfers

Problem	Transfers of clips with predefined lengths (such as loops or clips modified with BVW Insert Edit) will not copy all of the clip material if the transfer is initiated while the clip is still being recorded. (9966)
Workaround	Wait for the recording to complete before initiating the transfer. Avoid transferring clips being recorded in loop mode.
Problem	The API command PdrCopyMovie fails. (18420)
Workaround	Use the streaming API commands (Xfr) to move material between machines.

Disk Management

Problem	After unbinding a LUN, subsequent attempts to use existing clips or create new ones fail. (4635)
Workaround	If you unbind a LUN, you must create a new file system before you can record and play. Note that after creating a new file system, you can not use previously recorded material. Be sure to back up your material before performing this operation.
Problem	After unbinding a LUN, you can't bind any LUNs as Data. (10783)
Workaround	Close the Disk Utility window by clicking Finish, then reopen the window. You can now bind LUNs as Data.

Profile Protocol

No known problems at this time.

Louth Protocol

Problem	The Profile system ceases to respond correctly to Louth protocol commands when VdrPanel is minimized. (9621)
Workaround	Avoid minimizing VdrPanel when one or more panels are under Louth control.

Odetics Protocol

Problem	Occasionally, a clip may cue to a frame three or four frames earlier than the specified frame. (19123)
Workaround	Cue the clip again, or shuttle to the desired frame.

APIs

Problem	Using the FittedMedia commands (VdrAttachFittedMedia, VdrAttachFittedMediaWithMarks) on long-GOP clips may display unexpected frame sequences when a clip is played. (15802)	
Workaround	You can ensure correct playout in this situation by using I-frame only clips with FittedMedia commands.	
Diagnostics		
Problem	A number of messages similar to the following appear in the Profile log file (10782):	
	04 - 2301b025-I: Unknown Message	
Workaround	You can safely disregard these messages. They result from the new version of licensed internal code on the RAID systems.	
Problem	Profile applications do not start or do not operate correctly after running diagnostics.	
Workaround	You must restart Windows NT (Start Shut Down Restart the computer) after running diagnostics.	

